



City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

DEPARTMENT OF PUBLIC WORKS

NEW STORMWATER PRODUCTS COMMITTEE

Contents

Approved Rate Based SQUs	1
SQUs Removed from Approved List.....	3
Specific Design and Installation Requirements for Approved SQUs	6
Hydro International First Defense High Capacity	6
AquaShield Aqua-Swirl Xcelerator	6
Contech Cascade Separator.....	7
Hydro International First Defense Optimum	7
BioClean Debris Separating Baffle Box (DSBB)	7
StormTrap StormSettler	8
Appendix 1 - Design Treatment Flow Rate Determination for Stormwater Quality Flow Rate Determination	1
Appendix 2 - O&M Manual Checklist.....	1
Appendix 3 - Plan Checklist	1
Appendix 4 Technical Information Report/Drainage Report Checklist.....	1

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Approved Rate Based SQUs

For current Selection Guide, check:

<https://www.indy.gov/activity/public-works-specifications-and-manuals>

Performance Matrix for manufactured SQUs that are approved for use as post-construction water quality units in the City of Indianapolis and in compliance with the Stormwater Design and Construction Specifications Manual.

Only current NJDEP certified units listed below are considered "Approved". If NJDEP Certification lapses for an approved manufactured SQU listed below, it will no longer be considered an approved SQU for the City of Indianapolis regardless of being shown on the list below.

Approvals apply to units as documented by the data submitted for this certification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria.

Table 1. Approved Rate Based SQUs

Manufactured SQU	SQU System Model	Max Treatment Flow (cfs)	Max 10-yr On-Line Flow Rate (cfs)	Cleanout Depth (Inches)
Hydro International First Defense High Capacity	3-ft	0.85	1.84	9
	4-ft	1.5	3.24	9
	5-ft	2.35	5.08	9
	6-ft	3.38	7.3	9
	8-ft	6	12.96	9
Contech Cascade Separator	CS-3	1.02	2.27	9
	CS-4	1.8	4.03	9
	CS-5	2.81	6.29	9
	CS-6	4.05	9.07	9
	CS-10	11.3	25.3	9
	CS-12	16.2	36.3	9
Hydro International First Defense Optimum	3-ft	1.02	2.3	9
	4-ft	1.81	4.07	9
	5-ft	2.83	6.37	9
	6-ft	4.07	9.16	9
	8-ft	7.23	16.27	9
	10-ft	11.33	25.49	9

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Manufactured SQU	SQU System Model	Max Treatment Flow (cfs)	Max 10-yr On-Line Flow Rate (cfs)	Cleanout Depth (Inches)
BioClean Debris Separating Baffle Box (DSBB)	2-4	0.7	1.53	6
	2.5-5	1.1	2.4	6
	3-6	1.59	3.47	6
	4-6	2.11	4.6	6
	4-8	2.82	6.15	6
	5-10	4.4	9.6	6
	6-12	6.34	13.83	6
	7-14	8.63	18.83	6
	8-14	9.86	21.51	6
	8-16	11.27	24.59	6
	9-18	14.27	31.13	6
	10-18	15.85	34.58	6
	10-20	17.61	38.42	6
	10-22	19.37	42.26	6
	11-22	21.31	46.49	6
	11-24	23.25	50.73	6
	12-24	25.36	55.33	6
Bio Clean SciCloneX	SCX-4	1.82	3.68	12
	SCX-6	4.09	8.26	12
	SCX-8	7.27	14.69	12
	SCX-10	11.36	22.95	12
StormTrap StormSettler	SSet-3	0.79	1.58	7
	SSet-4	1.41	2.83	7
	SSet-5	2.19	4.4	7
	SSet-6	3.17	6.36	7
	SSet-7	4.3	8.6	7
	SSet-8	5.63	11.26	7
	SSet-10	8.78	17.56	7
	SSet-12	12.7	25.4	7
ADS Barracuda Max	S3	0.85	1.78	10
	S4	1.52	3.17	10
	S5	2.37	4.95	10
	S6	3.40	7.11	10
	S8	6.08	12.71	10
	S10	9.48	19.81	10

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

SQUs Removed from Approved List

Table 2. SQUs Removed from Approved List

NJDEP/NJCAT Certification has expired and no longer meet the City of Indianapolis Requirements

Manufactured SQU	SQU System Model	Max Treatment Flow (cfs)	Max 10-yr On-Line Flow Rate (cfs)	Cleanout Depth (Inches)
SeiClone	SC-3	0.39	0.78	9
	SC-4	0.7	1.4	9
	SC-5	1.09	2.18	9
	SC-6	1.57	3.14	9
	SC-7	2.14	4.28	9
	SC-8	2.8	5.6	9
	SC-9	3.54	7.08	9
	SC-10	4.37	8.74	9
	SC-11	5.29	10.58	9
	SC-12	6.3	12.6	9
CDS Technologies	CDS-3	0.52	1.04	9
	CDS-4	0.93	1.86	9
	CDS-5	1.5	3	9
	CDS-6	2.1	4.2	9
	CDS-7	2.8	5.6	9
	CDS-8	3.7	7.4	9
	CDS-10	5.8	11.6	9
	CDS-12	8.4	16.8	9
DVS	DVS-36C	0.56	1.12	9
	DVS-48C	1	2	9
	DVS-60C	1.56	3.12	9
	DVS-72C	2.25	4.5	9
	DVS-84C	3.06	6.12	9
	DVS-96C	4	8	9
	DVS-120C	6.25	12.5	9
	DVS-144C	9	18	9
HydroStorm by Hydroworks, LLC	HS-3	0.5	1	6
	HS-4	0.88	1.76	6
	HS-5	1.37	2.74	6
	HS-6	1.98	3.96	6
	HS-7	2.69	5.38	6
	HS-8	3.52	7.04	6
	HS-9	4.45	8.9	6
	HS-10	5.49	10.98	6
	HS-11	6.65	13.3	6
	HS-12	7.91	15.82	6

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Manufactured SQU	SQU System Model	Max Treatment Flow (cfs)	Max 10-yr On-Line Flow Rate (cfs)	Cleanout Depth (Inches)
Oldecastle NSBB-HVT	2-4	0.62	2.57	6
	3-6	1.4	5.8	6
	3-8	1.87	7.75	6
	4-8	2.49	10.31	6
	6-12	5.6	23.19	6
	6-13.75	6.42	26.59	6
	7-14	7.62	31.56	6
	7-15	8.17	33.84	6
	8-14	8.71	36.08	6
	8-16	9.96	41.25	6
	9-18	12.6	52.19	6
	10-17	13.22	54.76	6
	10-20	15.56	64.45	6
	12-21	19.6	81.18	6
	12-24	22.4	92.78	6
AquaShield Aqua Swirl Concentrator	AS-2	0.36	0.73	7
	AS-3	0.71	1.44	7
	AS-4	1.18	2.39	7
	AS-5	1.46	2.96	7
	AS-7	2.87	5.82	7
	AS-8	3.74	7.59	7
	AS-9	4.73	9.59	7
	AS-10	5.84	11.84	7
	AS-11	7.07	14.34	7
	AS-12	8.42	17.08	7
	AS-13	9.87	20.02	7
ADS Barracuda	S3	0.7	1.4	10
	S4	1.25	2.5	10
	S5	1.95	3.9	10
	S6	2.8	5.6	10
	S10	7.8	15.6	10
Hydro International Downstream Defender	4-ft	1.12	2.95	9
	6-ft	2.52	6.63	12
	8-ft	4.49	11.81	15
	10-ft	7	18.4	18
	12-ft	10.08	26.51	21

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Manufactured SQU	SQU System Model	Max Treatment Flow (cfs)	Max 10-yr On-Line Flow Rate (cfs)	Cleanout Depth (Inches)
StormTrap SiteSaver	STSS-1	1.08	2.33	6
	STSS-2	2.16	4.67	6
	STSS-3	3.24	7	6
	STSS-4	4.32	9.33	6
	STSS-5	5.4	11.66	6
	STSS-6	6.48	14	6
	STSS-7	7.56	16.33	6
	STSS-8	8.64	18.66	6
	STSS-9	9.72	21	6
	STSS-10	10.8	23.33	6
	STSS-11	11.88	25.66	6
	STSS-12	12.96	27.99	6
	STSS-13	14.04	30.33	6
	STSS-14	15.12	32.66	6
	STSS-15	16.2	34.99	6
	STSS-16	17.28	37.32	6
	STSS-17	18.36	39.66	6
	STSS-18	19.44	41.99	6
AquaShield Aqua-Swirl Xcelerator	XC-2	0.57	1.16	6
	XC-3	1.13	2.3	6
	XC-4	1.86	3.79	6
	XC-5	2.78	5.66	6
	XC-7	5.17	10.52	6
	XC-8	6.64	13.51	6
	XC-9	8.29	16.87	6
	XC-10	10.13	20.62	6
	XC-11	12.15	24.73	6
	XC-12	14.35	29.2	6
	XC-13	15.53	31.6	6

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Specific Design and Installation Requirements for Approved SQUs

These products have been approved by the Department for use on private development and public projects after June 14, 2024 with maximum treatment flow rates.

Please note the following criteria related to the specific unit.

Hydro International First Defense High Capacity

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Note, use of the units on City of Indianapolis projects shall be approved on a case-by-case basis by the project engineer.

Each submittal should include buoyancy calculations for the specific application.

AquaShield Aqua-Swirl Xcelerator

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Note, use of the units on City of Indianapolis projects shall be approved on a case-by-case basis by the project engineer.

Each submittal should include buoyancy calculations for the specific application.

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Contech Cascade Separator

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Note, use of the units on City of Indianapolis projects shall be approved on a case-by-case basis by the project engineer.

Each submittal should include buoyancy calculations for the specific application.

Hydro International First Defense Optimum

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Note, use of the units on City of Indianapolis projects shall be approved on a case-by-case basis by the project engineer.

Each submittal should include buoyancy calculations for the specific application.

Each unit will require additional measures to address retention of floatables. Units will also require additional measures to retain oils/ organics when those contaminants are expected such as in “hot spot” areas.

BioClean Debris Separating Baffle Box (DSBB)

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with ASTM C 857 and C 858 specifications.

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour (224% of the MTFR).

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

Note, use of the units on City of Indianapolis projects shall be approved on a case-by-case basis by the project engineer.

Each submittal should include buoyancy calculations for the specific application.

Bio Clean SciCloneX

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Each submittal should include buoyancy calculations for the specific application.

StormTrap StormSettler

Units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Note, use of the units on City of Indianapolis projects shall be approved on a case-by-case basis by the project engineer.

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Each submittal should include buoyancy calculations for the specific application.

Each unit will require additional measures to address retention of floatables. Units will also require additional measures to retain oils/ organics when those contaminants are expected such as in “hot spot” areas.

ADS Barracuda Max

Concrete units shall be installed in compliance with the current City of Indianapolis Stormwater Specifications Manual. The outer structure shall also comply with the current manual specifications.

HP / polypropylene outside structures will require class I bedding and backfill must be used and placed around the structures and connecting pipes in 8” lifts and compacted. In addition, polypropylene units will require an HS-20 load bearing slab (provided by ADS) that is to be supported by another concrete support collar poured on-site.

Manual. The outer structure shall also comply with the current manual specifications.

This approval applies to units as documented by the data submitted for this recertification review. Changes in materials of construction, overall unit dimensions, or dimensions of the internal components shall invalidate this approval and require submittal for re-approval under current evaluation criteria. This would include the square units which were listed but not tested or reviewed by NJCAT.

Units are approved for the 180° configuration, as verified by NJCAT. Grated inlets and multiple pipe side inlet configurations were not tested by the manufacturer.

The peak 10% exceedance (10-year) flow rate for on-line units may not exceed the maximum rate tested for scour.

Each submittal should include buoyancy calculations for the specific application, especially the polypropylene units.

Each unit will require additional measures to address retention of floatables. Units will also require additional measures to retain oils/ organics when those contaminants are expected such as in “hot spot” areas

Appendix 1 - Design Treatment Flow Rate Determination for Stormwater Quality Flow Rate Determination

The design flow rate for manufactured stormwater quality units (SQUs) shall be determined using the SCS runoff methodology as outlined below.

1. Delineate the watershed basin(s) to be served by the proposed SQU(s). Tabulate the total impervious and pervious areas. Please note impervious and pervious area runoff rates **MUST** be calculated as separate basins. The sizing calculation assumes the impervious area is connected directly to the SQU and the Tc calculation must be adjusted for this assumption (i.e. no flow over grass) for the impervious basin. This can be accomplished by creating two basins, one with an area equivalent to the total impervious area and the other with an area equivalent to the total pervious area of the delineated watershed to be served by the SQU.
2. Determine the time-of-concentration (Tc) using the TR-55 methodology (Worksheet 3, Chapter 200 Appendix of the City of Indianapolis Stormwater Specifications Manual) for each basin. A minimum 5-minute Tc may be assumed for the impervious basin.
3. Calculate the curve numbers (CN) for each basin, using CN=98 for the impervious basin.
4. Determine the peak discharge from the 0.3-inch storm using the appropriate Huff, 50% rainfall distribution (Storm duration 0 up to and including 6 hrs – 1st Quartile, 6.1 to 12 hrs – 2nd Quartile, 12.1 to 24 hrs – 3rd Quartile. See Table below for Huff ordinates.). A single hydrograph for each basin should be determined and all basin hydrographs added to determine the peak flow. Storm durations of 15-, 30- and 45 minutes as well as 1-, 2-, 3- 6- 12- and 24- hours should be checked to determine the peak SQU flow.

City of Indianapolis Stormwater Quality Unit (SQU) Selection Guide

Table IA. Huff Ordinates

Huff Rainfall Distribution Ordinates				
	Cumulative Percent of Storm Dept			
	h			
Cumulative Percent of Storm Time	1st Quartile (0 ≤ 6 hrs duration)	2nd Quartile (>6, ≤ 12 hrs duration)	3rd Quartile (>12, ≤ 24 hrs duration)	4th Quartile (>24 hrs duration)
0	0.00	0.00	0.00	0.00
5	16	3	3	2
10	33	8	6	5
15	43	12	9	8
20	52	16	12	10
25	60	22	15	13
30	66	29	19	16
35	71	39	232	19
40	75	51	27	22
45	79	62	32	25
50	82	70	38	28
55	84	76	45	32
60	86	81	57	35
65	88	85	70	39
70	90	88	79	45
75	92	91	85	51
80	94	93	89	59
85	96	95	92	72
90	97	97	95	84
95	98	98	97	92
100	100.00	100.00	100.00	100.00

Source: Bulletin 71, "Rainfall Frequency Atlas of the Midwest", Floyd A. Huff and James A. Angel, 1992

Appendix 2 - O&M Manual Checklist

In addition to the requirements listed in Section 102.06 of the Stormwater Specifications Manual, the following notes / maintenance items should be included in the Operations and Maintenance Manual (O & M Manual):

- _____ 1 Graphical and written description of sediment measuring procedure. This should include the use of a dipstick tube equipped with a ball valve (e.g. Sludge Judge®).
- _____ 2 Oil and other floatable materials removal procedure during routine cleanout.
- _____ 3 The O & M Manual should specify if entry into the SQU should be considered an OSHA confined space and guidelines followed.
- _____ 4 Detail drawing of proposed SQU, including floating debris capture device where applicable, should be included.
- _____ 5 Note in the manual to clean unit immediately if there is a hydrocarbon spill (e.g. gasoline or oil).
- _____ 6 The use of adsorbents should be addressed as appropriate.
- _____ 7 A note should be provided indicating disposal of all sediment must be in accordance with all federal, state and local requirements and should NOT be dumped into the storm sewer or a sanitary sewer.
- _____ 8 Other specific requirements per the manufacturer's recommendations.

Appendix 3 - Plan Checklist

The following items should be specified on all plans referencing a SQU submitted for approval by the City of Indianapolis:

- _____ 1 The minimum cover requirement as specified by the Stormwater Specifications Manual should be shown on the details for all connecting pipes.
- _____ 2 A minimum 6" stone base should be shown on the detail.
- _____ 3 The backfill should be specified as required by the manufacturer.
- _____ 4 Detail drawing of each SQU model, including floating debris capture device as applicable, per the manufacturer should be included on plans.
- _____ 5 Detail of connecting structures and diversion for off-line configurations should be included.
- _____ 6 A minimum 24" access opening must be shown.
- _____ 7 All construction plans shall show the SQUs installed with one inlet and one outlet pipe approximately 180 degrees apart unless the design report includes documentation the unit was tested by NJCAT and certified by NJDEP for the proposed layout. The inclusion of surface inlets must also include the testing and certification documentation.

Appendix 4 Technical Information Report/Drainage Report Checklist

The following requirements should be addressed in Technical Information Report/Drainage design reports:

- _____ 1 The design storm must not create a hydraulic tailwater condition on the SQU. A first flush hydraulic gradeline evaluation should be included in the report.
- _____ 2 The design storm should be the peak runoff for a 0.3-inch rainfall depth using the appropriate Huff, 50% rainfall distribution. The contributing watershed should be modeled with the pervious and impervious areas inputted as separate areas (i.e. not combined using a single curve number.)
- _____ 3 The 10-yr pipe capacity up- and downstream of all water quality structures should be documented with calculations to demonstrate the water surface for the 10-yr storm is below the crown of the pipe as required by the Stormwater Specifications Manual.
- _____ 4 Diversion structure design should be documented with calculations as appropriate.
- _____ 5 Buoyancy shall be addressed in the report.
- _____ 6 Traffic loading requirements should be addressed in the report.